

1) All Moderate Type laminate finish 2.5BHK R.s. ..690 Lakh

2) All veneer finish and melamine polish and deco paint 2.5 BHKcR.s..7.95 Lakh

We offer our best & competitive prices for furniture making for your flat at

Sr.no	Description	Nos
	MBR ROOM	
01	Providing and fixing wardrobe in 19mm Austin Gold Marine ply wood,with sliding shutters in 20mm Austin Gold ply wood . The internal of wardrobe shall be finished with .8mm thk white colour laminate and externally including shutters with of approved colour and make. The cost shall include necessary hardware, lipping beading, sliding door profile & toughened tinted glass etc all complete as directed and as perour drawings. For hard ware ref specifications given.(sliding door channel Hettich Top- , cupboard inside drawer, tandem box, soft,closing channel Hettcih & on out side 1mm thk color laminate	1
	Tv unit	
02	Providing and fixing TV unit in 19mm marine ply wood, internally finished with 1mm thk white laminate and external finished 1mm thk laminate. The unit shall include the draws and open shelves as shown in the drawing. The unit shall have 8mm ply wood cladding over the wall surface to have uniform	1
	King Size Bed	
03	Providing & Fixing of King Size Cot with 2side trolleys with Head Boardmade with 19mm Austin Gold Marine 710 ply wood with .8mm laminate finish inside & outer finsh with out side 1mm thk colour laminate ward. For hard ware ref specifications given.(hydraulic pump	1
04	Providing & Fixing of Side Tables with one drawer each made with 19Plywood with 1mm laminate finish with necessary hardware complete with all respects.	1
05	Providing headboard Fixing of 19mm ply with 1mm laminate finish withcloth as per design inclu. Wall Paneling	1
	Dressing Mirror	
06	Providing and fixing 6mm saint gobain mirror with 12mm backing ply wood. The mirror shall be fixed to ply wood with 3 Mtape. The cost shall include necessary teak wood beading , hard ware etc all complete as shown in the drawing.	1
	GBR ROOM	
01	Providing and fixing wardrobe in and & Dessing 19mm marine ply wood, with sliding shutters in 19mm ply wood frame work and cladded with 6 mm marine ply wood on both face. The internal of wardrobe shall be.finished.with1mm.thk.white.colour.laminate.and.externally including shutters with of approved colour and make. The cost shall include necessary hardware, lipping beading, 250 gsm pvc sheet covered on back side oof wardroe etc all complete as directed and as shown in drawings.Forhard ware ref specifications given.	1
	CBR ROOM	
01	Providing and fixing wardrobe in 19mm Austin Gold Marine ply wood,with sliding shutters in 20mm Austin Gold ply wood . The internal of wardrobe shall be finished with .8mm thk white colour laminate and externally including shutters with of approved colour and make. The cost shall include necessary hardware, lipping beading, sliding door profile & toughened tinted glass etc all complete as directed and as perour drawings. For hard ware ref specifications given.(sliding door channel Hettich Top- , cupboard inside drawer, tandem box, soft,closing channel Hettcih & on out side 1mm thk color laminate	1
	Bed	
02	Providing & Fixing of BED Size Cot with 2side trolleys with Head Boardmade with 19mm Austin Gold Marine 710 ply wood with .8mm laminate finish inside & outer finsh with out side 1mm thk colour	1

	laminate ward. For hard ware ref specifications given.(hydraulic pump	
03	Providing & Fixing of Side Tables with one drawer each made with 19 Plywood with 1mm laminate finish with necessary hardware complete with all respects.	1
04	Providing headboard Fixing of 19mm ply with 1mm laminate finish with cloth as per design inclu. Wall Paneling	1
	Dressing Mirror	
05	Providing and fixing 6mm saint gobain mirror with 12mm backing ply wood. The mirror shall be fixed to ply wood with 3 Mtape. The cost shall include necessary teak wood beading , hardware etc all complete as shown in the drawing.	1
	Living Room & Dining Hall	
	TV unit	
	Providing and fixing TV unit in 19mm marine ply wood, internally finished with 1mm thk white laminate and external finished with 4mm veneer. The unit shall include the draws and open shelves as shown in the drawing. The unit shall have 8mm ply wood cladding over the wall surface to have uniform	
	Crockery Unit	
	Providing & Fixing of Crockery Unit made with 19mm Plywood with 4mm Veneer finish with necessary hardware complete with all respects as per design inclu. Glass Shutter & Glass Shelves.	
	Kitchen Moderate Type	
01	Providing 19mm the plywood shutter, 12 mm the plywood bottom & side, inside surface finished in 1 mm the laminate & outside surface finished in High Gloss Marino 1 mm the Laminate or High Gloss ,soft close tandem channels, "Profile Handel & Necessary hardware as par detail drawing	1
02	Providing & Fixing of Loft Framed Shutters above lintel made with 19mm Waterproof ply with 1mm lamination finish with necessary hardware	1
03	Drawer HETTICH, MAKE, innotech Baskets 304 stainless still Material, 8 Basket Hob Side & tall unit 2400mm x 2200mm washing Machine Side Kitchen Middle storage	1
04	Providing & Fixing of Loft Framed Shutters above lintel made with 19mm Waterproof ply with 1mm lamination finish with necessary hardware	1
05	Basket innotech HETTICH	5
	Deep cleaning Extra	
	Total All	6.90 Lakh

- 1-Ply board: 19mm/25mm waterproof plywood Gurjan 710 BWP)
- 3-IN Side Laminate: 8mm thk
- 4 -out side Laminate: 1mm thk
- 5-Concealed Hinges: HAFELE make Opening angle 90 deg.
- 6-Sliding door sliding door system: Classic 100F (wood) HAFELE
- 7-Bottom guide will be in aluminium runner
- 8-Draw runners: HAFELE , HETTICH 40 kg Full extension
- 9-OR Quadro V6 Silent system Full extension runner HETTICH make
- 10-Draw runners: HAFELE 40 kg Full extension
- 11-Sliding Shutter Handle: Matt Nickel Flush Handle code no 152.23.681, 128mm
- 12-CNG Design and korean stone 4mm/12mm
- 13-Wardrobe tube oval profile 30x15mm chrome plated steel with tube support HETTICH
- 14-Basic cost for handle for openable shutter is Rs 350/No
- 15-Basic cost for Lock for sliding door and openable door is Rs. 500/No
- 16-All room&door Melamene metallic dekho

Note

The above shared quotation is subjected to the work discussed and agreed upon mutually, Any addition or reduction of work will amount to extra cost or reduction in the actual quote.

Terms & Condition

- a) 35% Advance on total project cost to start the work.
- b) 25% against completion of the internal body work,
- c) 25% Advance after the one month Or as per the work
- d) balance 5% against completion of the work

Water, Electricity,Storage Facility should be provided by the party.

Above prices will valid for 15days only.

The Project time line is 45days from the date of commencement of work.

Thanking You

Yours faithfully,

OWNERS SIGNATURE

for