## All Moderate Type laminate finish 2.5BHK R.s..7.90 Lakh All veneer finish and melamine polish and deco paint 2.5 BHKcR.s..9.5 Lakh

We offer our best & competitive prices for furniture making for your flat at

Sr.no	Description	Nos
	MBR ROOM	
01	Providing and fixing wardrobe in 19mm Austin Gold Marine ply wood, with sliding shutters in 20mm Austin Gold ply wood. The internal of wardrobe shall be finished with .8mm thk white colour laminate and externally including shutters with of approved colour and make. The cost shall include necessary hardware, lipping beading, sliding door profile & toughened tinted glass etc all complete as directed and as perour drawings. For hard ware ref specifications given.(sliding door channel Hettich Top-, cupboard inside drawer, tandem box, soft,closing channel Hettich & on out side 1mm thk color laminate	1
02	<b>Tv unit</b> Providing and fixing TV unit in 19mm marine ply wood, internally finished with 1mm thk white	1
02	laminate and external finished 1mm thk laminate. The unit shall include the draws and open shelves as shown in the drawing. The unit shall have 8mm ply wood cladding over the wall surface to have uniform  King Size Bed	'
03		1
03	Providing & Fixing of King Size Cot with 2side trolleys with Head Boardmade with 19mm Austin Gold Marine 710 ply wood with .8mm laminate finish inside & outer finsh with out side 1mm thk colour laminate ward. For hard ware ref specifications given.(hydraulic pump	
04	Providing & Fixing of Side Tables with one drawer each made with 19Plywood with 1mm laminate finish with necessary hardware complete with all respects.	1
05	Providing headboard Fixing of 19mm ply with 1mm laminate finish withcloth as per design inclu.  Wall Paneling  Dressing Mirror	
06	Providing and fixing 6mm saint gobain mirror with 12mm backing ply wood. The mirror shall be	1
	fixed to ply wood with 3 Mtape. The cost shall include necessary teak wood beading , hard ware etc all complete as shown in the drawing.	
	GBR ROOM	
01	Providing and fixing <b>wardrobe in and &amp; Dessing</b> 19mm marine ply wood, with sliding shutters in 19mm ply wood frame work and cladded with 6 mm marine ply wood on both face. The internal of wardrobe shall be finished with 1 mm. thk. white. colour. laminate. and externally including shutters with of approved colour and make. The cost shall include necessary hardware, lipping beading, 250 gsm pvc sheet covered on back side oof wardroe etc all complete as directed and as shown in drawings. Forhard ware ref specifications given.	1
	CBR ROOM	
01	Providing and fixing wardrobe in 19mm Austin Gold Marine ply wood, with sliding shutters in 20mm Austin Gold ply wood. The internal of wardrobe shall be finished with .8mm thk white colour laminate and externally including shutters with of approved colour and make. The cost shall include necessary hardware, lipping beading, sliding door profile & toughened tinted glass etc all complete as directed and as perour drawings. For hard ware ref specifications given.(sliding door channel Hettich Top-, cupboard inside drawer, tandem box, soft,closing channel Hettich & on out side 1mm thk color laminate  Bed	1
02	Providing & Fixing of BED Size Cot with 2side trolleys with Head Boardmade with 19mm Austin	1
	Gold Marine 710 ply wood with .8mm laminate finish inside & outer finsh with out side 1mm thk colour	'

	laminate ward. For hard ware ref specifications given.(hydraulic pump				
03	Providing & Fixing of Side Tables with one drawer each made with 19Plywood with 1mm laminate finish with necessary hardware complete with all respects.				
04	Providing headboard Fixing of 19mm ply with 1mm laminate finish withcloth as per design inclu.  Wall Paneling	1			
	Dressing Mirror				
05	Providing and fixing 6mm saint gobain mirror with 12mm backing ply wood. The mirror shall be fixed to ply wood with 3 Mtape. The cost shall include necessary teak wood beading, hardware etc all complete as shown in the drawing.	1			
	Living Room & Dining Hall				
	TV unit				
	Providing and fixing TV unit in 19mm marine ply wood, internally finished with 1mm thk white laminate and external finished with 4mm veneer. The unit shall include the draws and open shelves as shown in the drawing. The unit shall have 8mm ply wood cladding over the wall surface to have uniform				
	Crockery Unit				
	Providing & Fixing of Crockery Unit made with 19mm Plywood with 4mm Veneer finish with necessary hardware complete with all respects as per design inclu. Glass Shutter & Glass Shelves.				
	Kitchen Moderate Type				
01	Providing 19mm the plywood shutter,12 mm the plywood bottom & side, inside surface finished in 1 mm the laminate & outside surface finished in High Gloss Marino 1 mm the Laminate or High Gloss ,soft close tandem channels, "Profile Handel & Necessary hardware as par detail drawing	1			
02	Providing & Fixing of Loft Framed Shutters above lintel made with 19mm Waterproof ply with 1mm lamination finish with necessary hardware	1			
03	DrawerHETTICH,MAKE,innotech Baskets 304 stainless still Material,8Basket Hob Side & tall unit 2400mmx 2200mm washing Machine Side Kitchen Middle storage				
04	Providing & Fixing of Loft Framed Shutters above lintel made with 19mm Waterproof ply with 1mm lamination finish with necessary hardware				
05	Basket innotech HETTICH	5			
	POP Gypsum Board False Ceiling Work.				
	We are pleased to submit our quotation for the work of Gypsum Board False Ceiling with the				
	following specification including complete labour and material & Transporting charges.				
	Gypsum board false ceiling using other company sections with same specifications and same gauge 0.56mm thickness ceiling Patti, 0.80mm bottom (other company sections gypsum frame gypsum steel, jindal make etc.)				
	ELÉCTRICAL WORK				
01	Electrical Work (Wiring) p/f 1. Sq.mm wire HAVELLS for light point, 2.5 sq.mm wire for Circuit,2.5 sq.mm power point, 4 mm sq.mm for a.c., Telephone wiring, cat 6 for networking wiring provision,provision,or legrand standard quality & socket as per details drawing, material selection as per architect Approval				
	Electrical Fitting				
	Wiring, switch board Legrand Mylinc & plate, MCB Fixing, Holder & Ceiling rose fixing, with material: with labor charges p/f Ceiling down light fitting, LED Profile strips, indirect LED strips, wall fitting, Cabin Hanging Fitting, Range 1200 below,indirect led light & wall light ALL LED LIGHT,HAVELLS AND WIPRO				
	PAINTING WORK				
	Providing & applying Luster Paint of approved shade and colour in minimum three coat with Primer, includin preparation of surface, scrapping, sand papering etc.  Providing & applying Luster Paint of approved shade and colour in minimum three coat with Primer, includin				

preparation of surface,scrapping,sand papering etc.		
Deep cleaning Extra		
	Total All	7.90 Lakh

1-Ply board: 19mm/25mm waterproof plywood Gurjan 710 BWP)

3-IN Side Laminate: 8mm thk 4 –out side Laminate:1mm thk

5-Concealed Hinges: HAFELE make Opening angle 90 deg.

6-Sliding door sliding door system: Classic 100F (wood) HAFELE

7-Bottom guide will be in aluminium runner

8-Draw runners: HAFELE ,HETTICH 40 kg Full extension

9-OR Quadro V6 Silent system Full extension runner HETTICH make

10-Draw runners: HAFELE 40 kg Full extension

11-Sliding Shutter Handle: Matt Nickel Flush Handle code no 152.23.681,128mm

12-CNG Design and korean stone 4mm/12mm

13-Wardrobe tube oval profile 30x15mm chrome plated steel with tube support HETTICH

14-Basic cost for handle for openable shutter is Rs 350/No

15-Basic cost for Lock for sliding door and openable door is Rs. 500/No

16-All room&door Melamene metallic dekho

## **Note**

The above shared quotation is subjected to the work discussed and agreed upon mutually, Any addition or reduction of work will amount to extra cost or reduction in the actual quote.

## **Terms & Condition**

- a) 35% Advance on total project cost to start the work.
- b) 25% against completion of the internal body work,
- c) 25% Advance after the one month Or as per the work
- d) balance 5% against completion of the work

Water, Electricity, Storage Facility should be provided by the party.

Above prices will valid for 15days only.

The Project time line is 45days from the date of commencement of work. Thanking You

Yours faithfully,

**OWNERS SIGNATURE** 

for